

Mise à jour switch 3Com >>> Pour superStack 3° 4200

Description :

Cet article vous apprend comment mettre à jour un switch 3Com de type Superstack 3° 4200. Vous trouverez aussi le dernier firmware en téléchargement.

Mise à jour switch 3Com

>>> Pour superStack 3° 4200

Les Switchs de type SuperStack III 4200 family ne sont plus maintenu par 3COM ni par HP (nouveau propriétaire de 3Com). Vous trouverez donc le dernier firmware 3Com v.423_05 ci-dessous :



Dans le dossier deux firmwares sont présents, voir la release note pour savoir quel firmware utiliser.

- Via Internet Explorer ou Firefox, connectez-vous sur le switch.

(Connexion	
	192.168.118.253	

- Authentifiez-vous.

Authentification requise				
Le site http://192.168.118.253 demande un nom d'utilisateur et un mot de passe. Le site indique « device » Utilisateur : admin				
		Mot de passe :	••••••	
	OK Annuler			

- Cliquez sur le menu « Device View ».



- Dans l'arborescence, trouvez l'option « Software Upgrade ».



- Une nouvelle fenêtre s'ouvre.

🥹 Software Upgrade - Mozilla Firefox 📃 💷 💌
I92.168.118.253/dev01/html/softUpgrade.html
Filename
Server IP Address
This will upgrade the software in all units in the system.
After the upgrade has been completed the system will reset and will be temporarily unavailable.
OK Cancel

- Saisissez le nom du firmware et l'adresse IP du serveur TFTP.

🥹 Software Upgrad	e - Mozilla Firefox		
192.168.118.253	/dev01/html/softUpgrade.html		
Filename	t423_05.bin		
Server IP Address	192.168.118.69		
This will upgrade th	he software in all units in the system.		
After the upgrade h	After the upgrade has been completed the system will reset and will be		
temporarily unavail	able.		
	OK Cancel		

- Ouvrez votre serveur TFTP en configurant le dossier ou se trouve le firmware.

🔆 Tftpd32 by Ph. Jou	nin		
Current Directory C:\TFTP-Root Browse Server interfaces 192 168 118 69 Show Dir			
Tftp Server Tftp Clie	nt DHCP server S	uslog server Log v	viewer
peer	file	start time pro	gress
<	III		٩
About	Settings		Help

- Attendez le téléchargement et l'installation.



- Lorsque le switch a terminé il redémarre automatiquement.

6	Software Upgrade - Mozilla Firefox	5.71			X
	3 192.168.118.253/dev01/bin/SwUpg	radep.rhtm?File	eName	=t423	3_05 🏠
	Filename: Server IP Address: A power interrupt during software upg image on the device. In this event the via the software update utility. For mo guide supplied with your device. Software upgrade in progress Upgrade of unit 1 successful. Upgrade process successfully comp	t423_05.bin 192.168.118. grade may cau software shou re information, leted.	69 se a co JId be refer t	orrupi upgra o the	ted aded user
			ОК	Abo	rt

- Après le reboot, reconnectez-vous sur l'interface web pour vérifier que la version correspond bien à la version attendue : v3.05

	Device Summary : Unit 1
Name	sw-cmp_guerande-1
Туре	Switch 4200
Software Version	3.05
Hardware Version	04.01.01
IP Address	192.168.118.253

9 septembre 2013 -- N.Salmon -- article_254.pdf

